



ESTIMATE	#428
ESTIMATE DATE	Jan 6, 2023
TOTAL	\$120,000.00

CES Engineering Inc.
 CES Engineering Inc
 Tampa, FL 33647

CONTACT US

 (813) 210-4452
 rich@ceseng.us

ESTIMATE

Services	qty	unit price	amount
ONE TIME SERVICE - One Time Manual Service	1.0	\$120,000.00	\$120,000.00

· will handle all aspects of the site inspection for Phase 1, Phase 2 and Phase 3 at Aristida, in New Port Richey, FL. This includes clearing all swales that are suffocated with nuisance vegetation and silt. Clearing of all the FES and MES pipes ends, clearing of all the Basin structure with grates while removing any vegetation growth inside the sump. There are concrete weir structures throughout Aristida Phase 1, 2 and 3 within the swales and berms throughout rear yards that have excessive vegetation growth inside the skimmers. They require removal of vegetation so that proper flow can be engaged. Vegetation removal is required on the berm located by Jumper Ct and Alico Pass by image 3, 4 and 5 by weir, skimmer structures. Some berms are so overgrown that we can not locate some of the weir and skimmers structures and removal is required to ensure proper flow. The overall stormwater system has been neglected for some time, allowing for vegetation to take over the stormwater system and inhibiting the flow of water.

Price:

Phase One - \$45,000.00
Phase Two - \$50,000.00
Phase Three - \$25,000.00

Deposits schedule:

Phase one 50% deposit to begin work- \$22,500
Phase one 50% final payment before moving to phase two- \$22,500
Phase two 50% deposit to begin work- \$25,000
Phase two 50% final payment before moving to phase three- \$25,000
Phase three 50% deposit to begin work- \$12,500
Phase three 50% final payment upon completion- \$12,500

All payments for each phase are to be completed before moving on to next phase.

There is an aspect to this job that is "discovery" by nature. The information provided by CES indicates that some structures are unable to be located. If any change orders are needed, we will communicate immediately with pictures and clear outline of work needed to accomplish the task before that work is done.

· will de-root, remove, clear and haul-away all project related debris.

Services subtotal: \$120,000.00

Total **\$120,000.00**

All invoices are subject to a 10% penalty of total invoice price for every 30 days that payment is late.